



**F.no-IIIT-D/Bldg Proj/Boundary Wall/263/2018**

**Dated : 20.09.2018**

**NOTICE INVITING QUOTATION**

Sealed item rate quotations are invited for the following work on behalf of the Registrar IIIT Delhi from Eligible Contractors for **Boundary wall works behind New Academic block**, so as to reach the office of the undersigned upto 3PM on 28<sup>th</sup> Sept 2018 in envelope to be opened on the same day at 3:00 PM, in the office of the CE, A-208 2nd Floor of old Academic Block, IIIT-D Campus, Okhla Phase-III New Delhi-110020 in presence of the intending bidders who so wish to attend.

Location : Behind New Academic block  
Estimated cost of work put to tender : **Rs. 9.90 Lac**  
Time of completion : 30 Days

Earnest Money Deposit: Rs 19,800/- (Rupees Nineteen Thousand Eight Hundred only) is to be submitted with document as earnest money in favour of “**IIIT Delhi Collections**”

1. The works shall be carried out as per the relevant CPWD / BIS Standards and Terms and conditions, Specifications, BOQ and areas/locations as directed complete.
2. **Time Allowed:** 30 days from issue of work order.
3. Schedule of quantity: As per enclosed BOQ.
4. Clause 12 of GCC CPWD is applicable for EI/SI.
5. Contractor must visit site before quoting and fully satisfy himself of the site conditions.
6. Contractor must possess valid GST, PAN, and TIN no.
7. No T&P shall be issued to the Contractor .The contractor shall be provided with electricity and water at one point ,he shall make his own arrangements for further distribution of electricity , water supply and all other labour ,tools, plant and equipment etc as required for the works complete. Any damage done to existing walls /ceiling /floors /electrical /fire alarm/ fighting/plumbing equipment /building during execution shall be on the part of the Contractor.



8. Eligibility Criteria: The agencies must have satisfactory executed Civil works in Govt Deptts/PSU/Reputed Pvt sector /MNCs three works each of value 40% of estimated cost or two works each of 60% of estimated cost or one work of 80% of estimated cost during last 7 years. The applications not supported with requisite experience certificates shall not be entertained.
9. The priced bill of quantities, all duly signed by the authorized signatory of the firms.
10. Payment shall be made as per actual quantities of executed works against Final bill.
11. Security Deposit / Retention money shall be Five percent (5%) of the value of executed works and will be deducted from each and every payment made to the contractor against running account bill submitted for the work done at site. 50% of retention money will be released along with the payments of final bill and balance 50% will remain with Employer until the Defects Liability period is successfully over.
12. Defect Liability period 12 months from date of completion.
13. Conditional offers will not be accepted. The offer shall remain valid for 30days.
14. IIIT-D reserves the right to accept or reject any tender in part or whole without assigning any reasons thereof.
15. Contractor will ensure proper clearance of malba/ rubbish / debris created due to the works and clear site following completion of the works.

CE

**Bill of Quantity****BOQ for Boundary wall works behind New Academic block**

S.no	Items	Unit	Quantity	Rate	Amount
1	Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. (Note :- Cement content considered in this item is @ 330 kg/cum. Excess/less cement used as per design mix is payable/recoverable separately).				
1.1	All works upto plinth level	Cum	32		
1.2	All works above plinth level upto floor V level	Cum	20		
2	Steel reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete for all works i.e below /above plinth level.				
	Thermo-Mechanically Treated bars ( Fe-500)	Kg	5800		
3	Centring and shuttering including strutting, propping etc. and removal of form for:				
3.1	Footings	Sqm	20		
3.2	Walls	Sqm	160		
4	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed.				
4.1	All kinds of soil .	Cum	28		
4.2	Ordinary rock	Cum	28		
4.3	Hard rock ( blasting prohibited)	Cum	40		



5	Providing and laying in position ready mixed <b>plain cement concrete, using fly ash</b> and cement content as per approved design mix and manufactured in fully automatic batching plant and transported to site of work in transit mixer for all leads, having continuous agitated mixer, manufactured as per mix design of specified grade for plain cement concrete work, including pumping of R.M.C. from transit mixer to site of laying and curing, excluding the cost of centering, shuttering and finishing, including cost of curing, admixtures in recommended proportions as per IS : 9103 to accelerate/ retard setting of concrete, improve workability without impairing strength and durability as per direction of the Engineer - in - charge.				
	All works upto plinth level in M-10 grade plain cement concrete (cement content considered @ 220 kg/cum)	Cum	6		
6	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m & lift upto 1.5 m.	Cum	60		
7	Providing weep holes at 3 mtr c/c in RCC wall using UPVC 110 mm dia pipe	Nos	7		
	<b>Total</b>				
	<b>GST @ 18%</b>				
	<b>Total Amount (Inclusive all Taxes as GST, transportation VAT, Labour cess etc.)</b>				

In words \_\_\_\_\_