

INDRAPRASTHA INSTITUTE OF INFORMATION TECHNOLOGY DELHI (A state university established by Govt. of NCT of Delhi) Okhla, Phase III (Near Govind Puri Metro Station), New Delhi-110020, INDIA Telephone: +91 11 26907563/64/65 Website: <u>http://www.iiitd.ac.in</u>

F.no- IIITD/Bldg-Maintenance/Paints/264/2018

Dated: 16.05.2025

NOTICE INVITING QUOTATION (NIQ-16/2025)

Sealed item rate quotations are invited in **two** envelop system for the following work on behalf of the Registrar IIIT Delhi from Eligible Contractors for **NIQ for Civil Works including Internal Paint in Old & New Faculty Residence (Repair & Maintenance Works) at IIITD Campus.**, so as to reach the office of the undersigned upto 3PM on 23rd May 2025 to be opened on the same day at 3:30 PM, in the office of the PE&EO, A- 203 2nd Floor of Academic Block, IIIT-D Campus, Okhla Phase-III New Delhi-110020 in presence of the intending bidders who so wish to attend.

Earnest Money Deposit: Rs 9,850/- (Rupees Nine Thousand Eight Hundred and Fifty only) is to be submitted with document as earnest money in favour of "IIIT Delhi Collections" (except for those who are exempted by NSIC certifications (with Proof)) failing shall be treated as invalid and shall be liable for rejection. This will be enclosed in **Envelope- I.**

- 1. The works shall be carried out as per the relevant CPWD / BIS Standards and Terms and conditions, Specifications, BOQ and areas/locations as directed complete.
- 2. Time Allowed: 06 Months from issue of work order.
- 3. Schedule of quantity: As per enclosed BOQ.
- 4. Clause 12 of GCC CPWD is applicable for EI/SI.
- 5. Contractor must visit site before quoting and fully satisfy himself of the site conditions. No Compensation on account of any site difficulties will be entertained, at a later date, after award of the work.
- 6. Contractor must possess valid GST, PAN and TIN no.
- 7. No T&P shall be issued to the Contractor. The contractor shall be provided with electricity and water at one point, he shall make his own arrangements for further distribution of electricity, water supply and all other labour, tools, plant and equipment etc as required for the works complete. Any damage done to existing walls /ceiling /floors /electrical /fire alarm/ fighting/plumbing equipment /building during execution shall be on the part of the Contractor.
- 8. Eligibility Criteria: The agencies must have satisfactory executed civil paint works in Govt Deptts/PSU/Reputed Pvt sector /MNCs a three works each of value of Rs 1.97 Lac or two works each of value 2.96 Lac or one work of value 3.94 Lac during last 5 years to submit the experience certificates/work orders for the works and registration certificates with Govt. Depts. if any. The applications not supported with requisite experience certificates shall not be entertained.
- 9. The priced bill of quantities, all duly signed by the authorized signatory of the firms. This will be enclosed in **Envelope-II.**



- 10. Payment shall be made as per actual quantities of executed works against RA/Final bill at all locations as directed.
- 11. Defect Liability period 12 months from date of completion.
- 12. Security Deposit / Retention money shall be Two and Half percent (2.5%) of the value of executed works and will be deducted from each and every payment made to the contractor against running account bill submitted for the work done at site. retention money will be released with Employer until the Defects Liability period is successfully over.
- 13. Conditional offers will not be accepted. The offer shall remain valid for 60 days. The rates shall remain firm for a period of one year from date of award. The work order may be extended to cover additional areas at same rates as per institute requirements. No variation in rates shall be applicable.
- 14. Contractor should depute a qualified supervisor dedicated for this work, who will monitor and coordinate work from contractor's side and interact with the IIITD Engineers, responsible for supervision of work, on regular basis.
- 15. Rates to quoted are inclusive of all taxes, duties, cartage, loading unloading and shifting to location as called for
- 16. Contractor will take due permission for entry of all his workers in IIITD. No unauthorized person will be allowed to work inside.
- 17. During execution of work, Engineer may make minor changes in the scope of work as per site conditions or other reasons. Contractor will have no extra claim in his rates for the same.
- 18. All are supposed to use identified utilities of the Institute only.
- 19. The agency will seek prior approval of security guard and accompany by caretaker/guard for any work in the ladies' toilets/washrooms/restrooms.
- 20. Clarification/Queries, if any, can Be addressed to- Email ID: admin-project@iiitd.ac. in phone no01126907563/564/565, 011- 71985363/ 9773793610
- 21. IIIT-D reserves the right to accept or reject any tender in part or whole without assigning any reasons thereof.

PE&EO



INDRAPRASTHA INSTITUTE OF INFORMATION TECHNOLOGY DELHI (A state university established by Govt. of NCT of Delhi) Okhla, Phase III (Near Govind Puri Metro Station), New Delhi-110020, INDIA Telephone: +91 11 26907563/64/65 Website: <u>http://www.iiitd.ac.in</u>

SPECIAL TERMS AND CONDITIONS

- 1. Makes of various paints to be used by contractor will be according to the list of approved makes given. No other makes will be used by the contractor.
- 2. Contractor will first submit the shade cards of relevant make of paint to IIITD for approval of colour before procuring the paint in bulk.
- 3. No mixing will be allowed with stainer to achieve a particular colour. Contractor will procure direct colour paint of approved shade and apply directly.
- 4. Contractor will thoroughly clean all paint marks left here and there due to spilling and splashes of paint at no extra cost.
- 5. Contractor's job will also include removing of all malba and debris arising in the process of painting including washing of floor to remove stains of paint, at no extra cost.
- 6. No extra measurement factor will be applied for measurement of paint done on sand faced and rough cast plaster. Contractor will be paid on the basis of plain elevational area. Contractor, if he so desires can visit the site and see the actual surfaces of walls before quoting.
- 7. Contractor will arrange proper ladders, scaffolding and jhoolas (for painting at higher levels) at his own cost and will take all safety measures like safety belts, extra labour to hold ladders/Jhoolas etc. If it is observed that work is proceeding without adequate safety precautions, work may be stopped by engineer in charge and in such cases, contractor will be solely responsible for delay and its consequences thereof. The Contractor shall indemnify the IIITD in case of any damage loss or claims raised by any individual /Contractors on the works.
- 8. Contractor shall provide manufacturer's certificate for the material supplied at site and contractor shall bring 75% of theoretical quantity of required painting material before start of work.
- 9. The Contractors and his staff shall follow all the prevalent Covid Appropriate Behavior and laws of the land including the Environmental regulations enforced from time to time without any financial implication whatsoever on any side other than extension of time as decided by the Competent Authority.



INDRAPRASTHA INSTITUTE OF INFORMATION TECHNOLOGY DELHI (A state university established by Govt. of NCT of Delhi) Okhla, Phase III (Near Govind Puri Metro Station), New Delhi-110020, INDIA Telephone: +91 11 26907563/64/65 Website: http://www.iiitd.ac.in

TECHNICAL SPECIFICATIONS

- 1. For external paint, Contractor will thoroughly clean and wash the existing cement painted wall surfaces before starting paint at no extra cost. Contractor's quoted rates will include scrapping the loose paint and cleaning the entire surface with wire brush/sandpaper/broom.
- 2. Minor repairs (like repairing broken edges of walls, filling depressions etc.) with POP/wall care putty) will be carried out by contractor before starting painting work, at no extra cost. Same will be accounted for in his quoted rates.
- 3. Detailed technical specification for painting work with respect to materials & workmanship and mode of measurements will be as per IS codes and CPWD specifications, unless mentioned otherwise.
- 4. Thinner if required, may be added (not more than 10 %) in enamel paint with the prior permission of Engineer in Charge.
- 5. There should be proper time gaps (at least 4 hours) between two coats of paint to ensure drying of first coat of paint.
- 6. The approved quality, make & shade of paint shall be maintained by the Contractor throughout the work. The covering capacity ratio with respect to quantity of paint should be strictly adhered to by the Contractor as per specification. For any lapse / deficiency in this regard, a suitable deduction shall be made from the contractor's bill.
- 7. All painting material to be used should be of Premium/first quality.



INDRAPRASTHA INSTITUTE OF INFORMATION TECHNOLOGY DELHI

(A state university established by Govt. of NCT of Delhi) Okhla, Phase III (Near Govind Puri Metro Station), New Delhi-110020, INDIA Telephone: +91 11 26907563/64/65 Website: <u>http://www.iiitd.ac.in</u>

BOQ

| S.no. | Items | Unit | Qty | Rate | Amount |
|-------|--|------|------|------|--------|
| 1 | Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. | Sqm | 510 | | |
| | Make:JK/Birla white/Saint gobain | | | | |
| 2 | Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gram/litre, of approved manufacturer and of required shade and colour all complete to achieve even shade and colour : | | | | |
| | New work (two or more coats) over and including water thinnable priming coat with cement primer having VOC content less than 50 gram/litre | Sqm | 510 | | |
| | Make:Berger/ICI/Asian/Nerolac | | | | |
| 3 | Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. | Sqm | 510 | | |
| 4 | Distempering with 1st quality acrylic distemper (ready mixed) having VOC (Volatile Organic Compound) content less than 50 gram/ litre, of approved brand and manufacturer including applying additional coats wherever required to achieve even shade and colour | | | | |
| | Old work (one or more coats) | Sqm | 4630 | | |
| | Make:Berger/ICI/Asian/Nerolac | | | | |
| | AMOUNT | | | | |
| | <u>GST@18%</u> | | | | |
| | TOTAL AMOUNT WITH GST | | | | |

Note: All rate to be inclusive cost of Transportation, Labour, Materials etc. as required for satisfactory completion of work.