

F.no- IIIT-D/Bldg.Proj/416/2025-Civil


Dated: 05.03.2026

NOTICE INVITING QUOTATION (NIQ-05/2026)

Sealed item rate quotations are invited in **two** envelop system for the following work on behalf of the Registrar IIIT Delhi from Eligible Contractors for **NIQ for Shed Works on DG sets at IIITD Campus** so as to reach the office of the undersigned upto 3PM on **12th March 2026** to be opened on the same day at **3:30 PM**, in the office of the EE(C), A- 203 2nd Floor of Academic Block, IIIT-D Campus, Okhla Phase-III New Delhi-110020 in presence of the intending bidders who so wish to attend.

Earnest Money Deposit: Rs 9,760/- (Rupees Nine Thousand Seven Hundred Sixty only) is to be submitted with document as earnest money in favour of “**IIIT Delhi Collections**” (except for those who are exempted by MSME & NSIC certifications (with Proof)) failing shall be treated as invalid and shall be liable for rejection. This will be enclosed in **Envelope- I**.

1. The works shall be carried out as per the relevant CPWD / BIS Standards and Terms and conditions, Specifications, BOQ and areas/locations as directed complete.
2. **Time Allowed:** 30 days from issue of work order.
3. Schedule of quantity: As per enclosed BOQ.
4. Clause 12 of GCC CPWD is applicable for EI/SI.
5. Contractor must visit site before quoting and fully satisfy himself of the site conditions. No Compensation on account of any site difficulties will be entertained, at a later date, after award of the work.
6. Contractor must possess valid GST, PAN and TIN no.
7. No T&P shall be issued to the Contractor. The contractor shall be provided with electricity and water at one point, he shall make his own arrangements for further distribution of electricity, water supply and all other labour, tools, plant and equipment etc as required for the works complete. Any damage done to existing walls /ceiling /floors /electrical /fire alarm/ fighting/plumbing equipment /building during execution shall be on the part of the Contractor.
8. **Eligibility Criteria:** The agencies must have satisfactory executed Civil works in Govt Deptts/PSU/Reputed Pvt sector /MNCs a three works each of value of Rs 1.95 Lac or two works each of value 2.93 Lac or one work of value 3.90 Lac during last 5 years to submit the experience certificates/work orders for the works and registration certificates with Govt. Depts. if any. The applications not supported with requisite experience certificates shall not be entertained.
9. The priced bill of quantities, all duly signed by the authorized signatory of the firms. This will be enclosed in **Envelope- II**.



10. Payment shall be made as per actual quantities of executed works against RA/Final bill at all locations as directed.
11. Defect Liability period 12 months from date of completion.
12. Security Deposit / Retention money shall be Two and Half percent (2.5%) of the value of executed works and will be deducted from each and every payment made to the contractor against running account bill submitted for the work done at site. retention money will be released with Employer until the Defects Liability period is successfully over.
13. Conditional offers will not be accepted. The offer shall remain valid for 60 days. The rates shall remain firm for a period of one year from date of award. The work order may be extended to cover additional areas at same rates as per institute requirements. No variation in rates shall be applicable.
14. Contractor should depute a qualified supervisor dedicated for this work, who will monitor and coordinate work from contractor's side and interact with the IIITD Engineers, responsible for supervision of work, on regular basis.
15. Rates to quoted are inclusive of all taxes, duties, cartage, loading unloading and shifting to location as called for
16. Contractor will take due permission for entry of all his workers in IIITD. No unauthorized person will be allowed to work inside.
17. During execution of work, Engineer may make minor changes in the scope of work as per site conditions or other reasons. Contractor will have no extra claim in his rates for the same.
18. All are supposed to use identified utilities of the Institute only.
19. Clarification/Queries, if any, can Be addressed to- Email ID: admin-project@iiitd.ac.in in phone no01126907563/564/565, 011- 71985363/ 9773793610
20. Contractor shall visit the site before quoting.
21. IIIT-D reserves the right to accept or reject any tender in part or whole without assigning any reasons thereof.

EE(C)



BOQ

S.No.	Item Description	Unit	Qty	Rate	Amount
1.)	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
	Ordinary rock	cum	2.5		
2.)	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge	cum	1		
	Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)				
3.)	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :				
	1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size de rived from natural sources)	cum	0.5		
4.)	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
	Thermo-Mechanically Treated bars of grade Fe-500D or more	kg	35		
	Make- Tata Steel, Steel Authority of India Limited (SAIL), and Jindal Steel & Power (JSPL).				
5.)	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineerin-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required	sqm	240		
	Make-JSW Colouron+, Tata Shaktee, and Jindal Sabrang				

**INDRAPRASTHA INSTITUTE OF INFORMATION TECHNOLOGY DELHI**

(A state university established by Govt. of NCT of Delhi)

Okhla, Phase III (Near Govind Puri Metro Station), New Delhi-110020, INDIA

Telephone: +91 11 26907563/64/65

Website: <http://www.iiitd.ac.in>

6.)	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	kg	2090		
	Make- Tata Steel, Steel Authority of India Limited (SAIL), and Jindal Steel & Power (JSPL).				
7.)	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	sqm	130		
	Make:Berger/ICI/Asian/Nerolac				
	Total Amount				
	GST@18%				
	Total Amount with GST				

Note: All rate to be inclusive cost of Transportation, Labour, Materials etc. as required for satisfactory completion of work.

In words (Rs)

(_____)