



**F.no-IIIT-D/Bldg Proj/Boundary Wall/263/2018**

**Dated : 15.01.2019**

**NOTICE INVITING QUOTATION**

Sealed item rate quotations are invited in two envelop system for the following work on behalf of the Registrar IIIT Delhi from Eligible Contractors for **Barbed wire fencing work on top of existing boundary wall between Gate no. 4 to STP 2 at IIITD Campus**, so as to reach the office of the undersigned upto 3PM on 22<sup>nd</sup> Jan 2019 in envelope to be opened on the same day at 3:00 PM, in the office of the CE, A-208 2nd Floor of old Academic Block, IIIT-D Campus, Okhla Phase-III New Delhi-110020 in presence of the intending bidders who so wish to attend.

Location : Near gate no. 4 of IIITD campus.

Estimated cost of work put to tender : **Rs 5.50 Lac**

Time of completion : 30 Days

Earnest Money Deposit: Rs 11,000/- (Rupees Eleven Thousand only) is to be submitted with document as earnest money in favour of “**IIIT Delhi Collections**” This will be enclosed in Envelope- I.

1. The works shall be carried out as per the relevant CPWD / BIS Standards and Terms and conditions, Specifications, BOQ and areas/locations as directed complete.
2. **Time Allowed:** 30 days from issue of work order.
3. Schedule of quantity: As per enclosed BOQ. To be filled in neat handwriting and placed in **Envelope- II.**
4. Clause 12 of GCC CPWD is applicable for EI/SI.
5. Contractor must visit site before quoting and fully satisfy himself of the site conditions.
6. Contractor must possess valid GST, PAN, and TIN no.
7. No T&P shall be issued to the Contractor .The contractor shall be provided with electricity and water at one point ,he shall make his own arrangements for further distribution of electricity , water supply and all other labour, tools, plant and equipment etc as required for the works complete. Any damage done to existing walls /ceiling /floors /electrical /fire alarm/ fighting/plumbing equipment /building during execution shall be on the part of the Contractor.



---

**8. Eligibility Criteria: documents will be enclosed in Envelope I.**

- i. The agencies must have satisfactory executed similar Civil works in Govt Deptts/PSU/Reputed Pvt. sector /MNCs three works each of value 40% of estimated cost or two works each of 60% of estimated cost or one work of 80% of estimated cost during last 7 years. The applications not supported with requisite experience certificates shall not be entertained.
  - ii. The eligible contractors must have carried out at least one similar works costing 2.2 Lacs or more in IIIT-D/Govt Deptts/PSU /State or Central Autonomous bodies are to submit the experience certificates for the works and registration certificates with Govt. Depts.
  - iii. Shall have an average annual financial gross turnover of Rs. 14 Lacs on similar works during the last three consecutive financial years ending 31st March 2018. Certificate of CA to be enclosed.
  - iv. Shall not have incurred any loss in more than two years during the last five years ending 31st March 2018.
  - v. Solvency certificate from bank of amount equal to 2.2 Lacs is to be submitted.
  - vi. An undertaking on having visited site must be enclosed.
9. The priced bill of quantities, all duly signed by the authorized signatory of the firms. This will be enclosed in **Envelope- II.**
10. Payment shall be made as per actual quantities of executed works against running advance/Final bill.
11. Security Deposit / Retention money shall be Five percent (5%) of the value of executed works and will be deducted from each and every payment made to the contractor against running account bill submitted for the work done at site. 50% of retention money will be released along with the payments of final bill and balance 50% will remain with Employer till the Defects Liability period is successfully over.
12. Defect Liability period shall be for 12 months from date of completion.
13. Conditional offers will not be accepted. The offer shall remain valid for 30days.
14. IIIT-D reserves the right to accept or reject any tender in part or whole without assigning any reasons thereof.
15. Contractor will ensure proper clearance of malba/ rubbish / debris created due to the works and clear site following completion of the works.
16. Minor trimming of vegetation as required by the agency for execution for the work will be executed by the agency at no extra cost.



**GENERAL INSTRUCTIONS FOR SITE VISIT**

I, \_\_\_\_\_, aged \_\_\_ years, son/daughter of \_\_\_\_\_, presently residing at \_\_\_\_\_ and authorized by \_\_\_\_\_ (name of tenderer) ("Tenderer") to solemnly affirm on behalf of the Tenderer, solemnly affirm on oath as hereunder:

The Tenderer confirms that the Tenderer has duly undertaken the visit of the proposed project site of IIITD located at Okhla Phase III, New Delhi,.

The Tenderer has inspected and examined its surroundings and has satisfied itself about the site conditions and site logistics. The Tenderer confirms that it is aware of the ground conditions and nature of the site, means of access to the site and the accommodation area required for establishing the labour camp. The Tenderer agrees and confirms it shall be solely responsible for arranging and maintaining the afore-mentioned at its own cost including all materials, tools & plants, water, electricity, access, facilities for workers and all other services required for executing the Work unless otherwise specifically provided for in the contract documents.

The Tenderer confirms and agrees that the submission of the tender implies that the requisite site visit has already been undertaken and that the Tenderer has acquainted itself with the local conditions and other factors having a bearing on the execution of the Work.

DEPONENT

VERIFICATION

I, \_\_\_\_\_, aged \_\_\_ years, son/daughter of \_\_\_\_\_, presently residing at \_\_\_\_\_ and authorized by Tenderer verify that the information mentioned above is true and correct to the best of my knowledge and belief.

DEPONENT

**Bill of Quantity****BOQ for Barbed wire fencing work on top of existing boundary wall between gate no. 4 to STP 2**

S.no	Items	Quantity	Unit	Rate	Amount
1	Fencing with R.C.C. post placed at required distance, embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post one side only, provided with horizontal lines and two diagonals of barbed wire weighing 9.38 kg per 100 metres (minimum), between the two posts fitted and fixed with G.I. staples on wooden plugs or G.I. binding wire tied to 6 mm bar nibs fixed while casting the post. (cost of R.C.C. posts, struts, earth work and concrete to be paid for separately) :- Payment to be made per metre cost of total length of barbed wire used.				
	With G.I. barbed wire	2880	metre		
2	Dismantling old concertina wire with Y angles from top of the boundary wall including making rolls and stacking within 50 metres lead	200	metre		
3	R.C.C. Standards post/ struts/rails/ pales of mix 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 12.5 mm nominal size) with wooden plugs or 6mm bar nibs wherever required as per direction of Engineer-in- charge (cost of earth works in excavation, concrete works in foundation to be paid separately).	3.5	cum		
4	Supplying and fixing turn buckles and straining bolts for barbed wire fencing.	30	each set		
5	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement.				
	"RCC work in Beam band on top of existing boundary wall of 1:1.5:3 (1 cement: 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size).	27	cum		



---

6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete in RCC wall				
	Thermo-Mechanically Treated bars of grade Fe-500D or more	2250	Kg		
7	Centering and shuttering including strutting, propping etc. and removal of form work for :				
	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc.	125	sqm		
8	Dismantling of RRM wall for fixing of RCC posts.	80	No.		
	<b>Total Amount</b>				
	<b>GST @ 18%</b>				
	<b>Total Amount (Inclusive all Taxes as GST, transportation VAT, Labour cess etc.)</b>				

In words \_\_\_\_\_